7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Items of work.	Per.	Quantity.	Quantity.
Earthwork excavation and filling in basement	C. yd.	408	73
Foundation, basement, superstructure, coursed rubble in mortar ...	C. ft.	15,031	2,363
Superstructure, coursed rubble in clay	,,	...	4,721
Arch work, brick in mortar	,,	205	25
Brick in clay	,,	...	217
Coping with brick in mortar	R. ft.	...	60
Stone slabs 6″ face dressed for cill and lintel to doors, etc. ...	S. ft.	1,164	30
Do 4½″ do do ...	,,	...	105
Plastering with chunam	Sqr.	133·56	...
Whitewashing	,,	74·54	...
Color washing	,,	59·02	...
Pointing with chunam	,,	...	81·30
Flooring with Mangalore tiles 8″ square 1″ thick	,,	26·36	...
Do gravel 6″ deep well ramned	C. yds	...	17
Roofing with Mangalore tiles including reepers and chunam border, pointing, joints with cement.	Sqr.	49·36	12·25
Ridging roof set in cement	R. ft.	260	50½
Wood work, Burma teak wrought and put up	C. ft.	495·45	...
Do honne do do	,,	...	118⅝
Eave boards	R. ft.	481	117
Ceiling with pine wood plank ½″ thick	Sqr.	22·46	...
Teak wood doors battened 1½″ thick with iron fixture and complete with painting.	S. ft.	721	...
Do double do do ...	,,	72	...
Do windows, battened and glazed shutter with iron bars.	,,	286	...
Do ventilator glazed with iron bars, etc., complete and circular windows in gable	,,	175	...
Honne wood doors, windows and ventilators, etc.	S. ft.	...	161½
Zinc gutters to valley 18′ wide	R. ft.	72	...
Pillars 6 and half pillars 8 of teak wood 9″ × 9″ and 6″ × 9″ and 8′ high, complete.	L. S.	6 and 8	...
Wooden or stone pillars to Out Houses 12″ × 6″ × 11′ height of stone.	Each.	...	2
Levelling site etc.	Lump sum.		
Finials	Each.	4	...
Latrine	Lump sum.		
Painting to doors, windows and ventilators etc., (chacolate) ...	Sqr.	27·63	...

S. A. RAMASAMI, *for Executive Engineer.*

Dated 7th December 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 12 noon on 31st December 1904, for restoring Jonnagatta tank Registered No. 345, Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1905.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar, between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates tendered should include royalty on stones, etc., removed from Government lands, to be paid to the Government.

4. Each tender must be accompanied by a deposit of rupees two hundred, in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Jonnagatta tank Register No. 345, Kolar" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

ABSTRACT.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earthwork	C. yds.	20,696
Clearing silt, removing boulders and re-filling the same with new earth.	,,	19,000
Baling waters	Lump sum.	
Fixing old and new grade stone	Do	
Rough stone, new	C. yds.	3,368
Do old	,,	200
Turfing	S. yds.	12,188
Gravel backing	C. yds.	1,122
Sluices—		
Repairing 1, 2 and 3 sluices	Lump sum.	
Building a sluice in right weir in place of No. 4 sluice ...	Do	
Waste weirs—		
Waste weir, right, 350 feet long —		
Earthwork	C. yd.	5,834
Concrete in surki mortar	C. ft.	2,049
Brick in surki mortar	,,	4,541
Stone slabs	Sq. ft.	895
Jelly packing	Lump sum.	
Burnt stone in surki mortar	C. ft.	1,080
Burnt stone, dry, new	C. yds.	204
Do old	,,	200
Rough stone, new	,,	15
Plastering with chunam	Sq.	16·00
Pointing with chunam	,,	7·00
Waste weir, left, 450 feet long—		
Earthwork	C. yds.	1,191
Concrete in surki	C. ft.	1,603
Brick in surki	,,	4,612
Burnt stone in surki	,,	1,884
Burnt stone slabs 6" thick	S. ft.	860
Burnt stone, dry	C. yds.	1760
Rough stone, new	,,	60
Plastering with chunam	Sq.	20·00
Pointing with chunam	,,	10·00
Dismantling a portion of the existing weir to join in the new proposed extension.	Lump sum.	
Clearing approaches and draft	Do	

S. RAMASWAMI,
for *Executive Engineer.*

HASSAN DIVISION.

Dated 8th December 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 3rd January 1905, for restoring Kattarigatta tank Registered No. 72—113 of Channarayapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1905.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan, between the hours of 11 A.M. and 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kattarigatta tank, Registered No. 72—113, of Channarayapatna Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.